

# CALARC® DIVISION

# **WALL CAP DETAILS**

CLASSIC WALL CAP BY STEPSTONE®	PAGE #
Classic Wall Cap - General Details	3
Classic Wall Cap - Sizes	4
Classic Wall Cap - General Radiuses	5
Classic Wall Cap with Radius 10-1/4" Width	6
Classic Wall Cap with Radius 12" Width	7
Classic Wall Cap with Radius 14" Width	8
Classic Wall Cap with Radius 16" Width	9
Classic Wall Cap with Radius 24" Width	10
Classic Pilaster Cap - General Details	11
Classic Pilaster Cap - Sizes, Flat and Peaked	12
Classic Pilaster Cap with Center Hole	13
Classic Fire Pit Cap	14
SONORASTONE® WALL CAP - PEAKED	
Sonorastone® Peaked Wall Cap - General Details	15
Sonorastone® Peaked Wall Cap - Sizes	16
Sonorastone® Peaked Pilaster Cap - Sizes	17
SONORASTONE® WALL CAP - FLAT	
Sonorastone® Flat Wall Cap - General Details	18
Sonorastone® Flat Wall Cap - Sizes	19
Sonorastone® Flat Wall Cap - General Radiuses	20
Sonorastone® Flat Wall Cap with Radius 7-1/4" Width	21
Sonorastone® Flat Wall Cap with Radius 9-1/4" Width	22
Sonorastone® Flat Wall Cap with Radius 13-1/4" Width	23
Sonorastone® Flat Pilaster Cap - Sizes	24
Sonorastone® Low Wall Seat	25
Sonorastone® Fire Pit Cap	26
SQUARE MODULAR WALL CAP	
Square Modular Wall Cap - Straight	27
Square Modular Wall Cap - Corner	28
Square Modular Wall Cap - End	29
Square Modular Pilaster Cap	30

Page 1



**Nationwide Distribution** 

# CLASSIC WALL CAP

8" x 24" x 2-1/2"

10-1/4" x 24" x 2-1/2"

12" x 24" x 2-1/2"

14" x 24" x 2-1/2"

16" x 24" x 2-1/2"

24" x 24" x 2-1/2"

# **CLASSIC PILASTER CAP-FLAT**

14" x 14" x 2-1/2"

16" x 16" x 2-1/2"

19" x 19" x 2-1/2"

22" x 22" x 2-1/2"

24" x 24" x 2-1/2"

28" x 28" x2-1/2"

# CLASSIC PILASTER CAP-PEAKED

14" x 14" x 3-3/4"

16" x 16" x 4"

19" x 19" x 4-1/4"

22" x 22" x 4-3/8"

24" x 24" x 4-1/2"

28" x 28" x 5"

# SONORASTONE® PEAKED WALL CAP

 $9-1/4" \times 24" \times 3"$ 

12-1/4" x 24" x 3-1/4"

16-1/4" x 24" x 3-3/4"

# SONORASTONE® FLAT WALL CAP

10" x 24" x 2-1/2"

12" x 24" x 2-1/2"

16" x 24" x 2-1/2"

# SONORASTONE® PILASTER CAP-PEAKED

18-1/4" x 18-1/4" x 3"

24-1/4" x 24-1/4" x 3"

24-1/4" x 18-1/4" x 3"

# SONORASTONE® PILASTER CAP-PEAKED

13-1/4" x 13-1/4" x 3-1/2"

18-1/4" x 18-1/4" x 4"

22-1/4" x 22-1/4" x 4-3/8"

24-1/4" x 24-1/4" x 4-3/4"

# SQUARE MODULAR WALL CAP

 $7-1/4'' \times 24'' \times 3-3/8''$ 

9-1/4" x 24" x 3-3/8"

13-1/4" x 24" x 3-3/8"

20-1/4" x 24" x 3-3/8"

## SQUARE MODULAR PILASTER CAP

13" x 13" x 3-3/8"

15" x 15" x 3-3/8"

20" x 20" x 3-3/8"

23" x 23" x 3-3/8"


27" x 27" x 3-3/8"

800.572.9029 stepstoneinc.com

Page 2







## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP & NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 3



Detail



## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP & NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 4







### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP & NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 5



CALARC® DIVISION



### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP & NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 6







### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP & NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 7







### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP & NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 8



ARC® DIVISION



## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP & NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 9



# CALARC® DIVISION



## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP & NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 10








### NOTES:

- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP AND NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 11

## **Nationwide Distribution**



SELECT DESIRED QTY. FLAT

WIDTH 14" x 14" SQ.

WIDTH 16" x 16" SQ.

WIDTH 19" x 19" SQ.

WIDTH 22" x 22" SQ.

WIDTH 24" x 24" SQ.

WIDTH 28" x 28" SQ.

SELECT DESIRED QTY. PEAKED

WIDTH 14" x 14" SQ. (THICK,  $3\frac{3}{4}$ ")

WIDTH 16" x 16" SQ. (THICK, 4")

WIDTH 19" x 19" SQ. (THICK,  $4-\frac{1}{4}$ ")

WIDTH 22" x 22" SQ. (THICK,  $4-\frac{3}{8}$ ")

WIDTH 24" x 24" SQ. (THICK,  $4-\frac{1}{2}$ ")

WIDTH 28" x 28" SQ. (THICK, 5")

## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP AND NOSE, SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.




Page 12







Detail



SELECT DESIRED QTY. FLAT

WIDTH 14" x 14" SQ.

WIDTH 16" x 16" SQ.

WIDTH 19" x 19" SQ.

WIDTH 22" x 22" SQ.

WIDTH 24" x 24" SQ.

WIDTH 28" x 28" SQ.

SELECT DESIRED QTY. PEAKED

WIDTH 14" x 14" SQ. (THICK,  $3\frac{3}{4}$ ")

WIDTH 16" x 16" SQ. (THICK, 4")

WIDTH 19" x 19" SQ. (THICK,  $4-\frac{1}{4}$ ")

WIDTH 22" x 22" SQ. (THICK,  $4-\frac{3}{8}$ ")

WIDTH 24" x 24" SQ. (THICK,  $4-\frac{1}{2}$ ")

WIDTH 28" x 28" SQ. (THICK, 5")

## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP AND NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.
- 5. CENTER HOLE IS STANDARD  $2\frac{1}{2}$ " x  $2\frac{1}{2}$ ", CUSTOM HOLE AVAILABLE.



Page 13



Nationwide Distribution



## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICES.
- 3. SMOOTH FINISH ON TOP & NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.
- 5. WE DO NOT RECOMMEND THE USE OF OUR CONCRETE PRODUCTS IN ENVIRONMENTS THAT WILL HEAT THE CONCRETE TO MORE THAN 200 DEGRESS, DIRECT EXPOSURE TO A FIRE'S FLAME FOR AN EXTENDED PERIOD OF TIME WILL DAMAGE THE CONCRETE. INSTALLATIONS SUBJECTING STEPSTONE'S PRECAST PIECES TO EXCESSIVE HEAT WILL VOID THE MANUFACTURER'S WARRANTY AND STEPSTONE, INC WILL NOT REPLACE ANY DAMAGED PRODUCT.



Page 14







## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SONORASTONE® FINISH ON TOP & SIDES.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 15

RC® DIVISION






- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SONORASTONE® FINISH ON TOP & SIDES.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.




Page 16








SIDE



**ISOMETRIC** 



TOP

### LENGTH: SQUARE

SIZE: 13-1/4" SQ. HEIGHT: 3-1/2" SIZE: 18-1/4" SQ. HEIGHT: 4" SIZE: 22-1/4" SQ. HEIGHT: 4-3/8" SIZE: 24-1/4" SQ. HEIGHT: 4-3/4"


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST, LENGTHS ARE APPROXIMATE, SOME VARIATIONS
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SONORASTONE® FINISH ON TOP & SIDES.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 17



# $R C^{\otimes}$ division




- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SONORASTONE FINISH ON TOP & SIDES.
  4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 18

RC® DIVISION







## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SONORASTONE FINISH ON TOP & SIDES.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.




Page 19









### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY
- 3. SONORASTONE FINISH ON TOP & SIDES.
  4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.




Page 20










### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SONORASTONE FINISH ON TOP & SIDES.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 21








## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SONORASTONE FINISH ON TOP & SIDES.
  4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.




Page 22











## NOTES:

- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SONORASTONE FINISH ON TOP & SIDES.
  4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 23




- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST, LENGTHS ARE APPROXIMATE, SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SONORASTONE<sup>®</sup> FINISH ON TOP & SIDES.
  4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 24








- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY
- 3. SONORASTONE® FINISH ON TOP & SIDES.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 25



Nationwide Distribution R C® DIVISION



### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICES.
- 3. SONORASTONE FINISH ON TOP AND SIDES.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.
- 5. WE DO NOT RECOMMEND THE USE OF OUR CONCRETE PRODUCTS IN ENVIRONMENTS THAT WILL HEAT THE CONCRETE TO MORE THAN 200 DEGRESS. DIRECT EXPOSURE TO A FIRE'S FLAME FOR AN EXTENDED PERIOD OF TIME WILL DAMAGE THE CONCRETE. INSTALLATIONS SUBJECTING STEPSTONE'S PRECAST PIECES TO EXCESSIVE HEAT WILL VOID THE MANUFACTURER'S WARRANTY AND STEPSTONE, INC WILL NOT REPLACE ANY DAMAGED PRODUCT.





Page 26



# **Nationwide Distribution**







THICKNESS: 3-3/8"

LENGTH: 24"

WIDTH A:7-1/4" WIDTH B:5-3/4"


### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP AND SIDES. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.





# Nationwide Distribution





# SIDE


THICKNESS: 3-3/8"


LENGTH: 10" SQ. WIDTH:7-1/4" WIDTH:5-3/4"

LENGTH: 12" SQ. WIDTH A: 9-1/4" WIDTH B: 7-3/4"

LENGTH: 16" SQ. WIDTH A: 13-1/4" WIDTH B: 11-3/4"


LENGTH: 23" SQ. WIDTH A: 20-1/4" WIDTH B: 18-3/4"





### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP AND SIDES. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



Page 28



## **Nationwide Distribution**




## NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP AND SIDES. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.





Page 29











THICKNESS: 3\frac{3}{8}"

INSIDE RADIUS:	OUTSIDE RADIUS:	OUTSIDE LENGTH:
15 <u>1</u> "	24 <del>3</del> "	37 <u>5</u> "
39 <del>1</del> "	48 <u>3</u> "	24 <del>3</del> "
63 <u>1</u> "	72 <del>3</del> "	27 <del>7</del> "
87 <u>1</u> "	96 <u>3</u> "	24 <del>3</del> "

### NOTES:


- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST, LENGTHS ARE APPROXIMATE, SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.





Page 30




# Nationwide Distribution









## THICKNESS: 3\frac{3}{8}"

LENGTH A:	LENGTH B:	WIDTH A:	WIDTH B:
13 <u>1</u> "	12"	13 <u>1</u> "	12"
15 <u>1</u> "	14"	15 <u>1</u> "	14"
20"	18 <del>1</del> "	20"	18 <u>1</u> "
$23\frac{1}{2}$ "	22"	23 <u>1</u> "	22"
27 <del>1</del> "	26"	27 <u>1</u> "	26"

## NOTES:

- 1. PRECAST UNITS ARE INDIVIDUALLY HAND CAST. LENGTHS ARE APPROXIMATE. SOME VARIATIONS ARE EXPECTED.
- 2. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH GENERALLY ACCEPTED MASONRY PRACTICE.
- 3. SMOOTH FINISH ON TOP AND NOSE. SANDBLAST FINISH AVAILABLE.
- 4. PRECAST UNITS MAY BE CUT TO FIT FIELD CONDITIONS.



# SQUARE MODULAR PILASTER CAP

SCALE: N.T.S.

Page 31