

BID SCHEDULE **(ADDENDUM NO. 1)**
FOR
SANTA TERESA HIGH SCHOOL
DW INFRASTRUCTURE - PLAY COURT IMPROVEMENTS
PROJECT NO. Z-070-705

<u>ITEM</u>	<u>DESCRIPTION</u>	<u>QTY.</u>	<u>UNIT</u>	<u>UNIT COST</u>	<u>TOTAL</u>
1.	Excavate Existing Material to a Depth of 6 Inches; Lime/Cement Treat to a Depth of 8 Inches and Place 3-1/2 Inch HMA	41,700	SF	\$_____	\$_____
2.	Apply Acrylic Seal Coat	41,700	SF	_____	_____
3.	Remove and Replace PCC Pad with Integral Curb and Gutter	100	SF	_____	_____
4.	Remove and Replace PCC Curb and Gutter	5	LF	_____	_____
5.	Remove and Replace PCC Curb	10	LF	_____	_____
6.	Install PCC Sidewalk	25	SF	_____	_____
7.	Remove Existing Water Fountain and Install New ELKAY EZH20 Bottle Filling Station; Evergreen in Color	1	EA	_____	_____
8.	Excavate and Remove Existing Vegetation, Regrade, Place Top Soil and Reseed	3,500	SF	_____	_____
9.	Remove and Dispose of Existing Trees, Roots and Root Balls	5	EA	_____	_____
10.	Remove and Replace (or) Install Redwood Headerboard	625	LF	_____	_____
11.	Remove Existing Posts and Fencing; Install New 12 Foot High Chain Link Fencing with New Gates and Privacy Netting	990	LF	_____	_____
12.	Remove and Dispose of Existing Tennis Court Hardware; Install New Tennis Court Hardware	6	EA	_____	_____
13.	Protect Existing Electrical Lines and Junction Boxes During Construction; Refasten to New Fencing	---	LS	---	_____
14.	Remove Existing Electrical Boxes and Conduit; Cut and Cap Electrical Lines and Place in Junction Box	---	LS	---	_____

<u>ITEM</u>	<u>DESCRIPTION</u>	<u>QTY.</u>	<u>UNIT</u>	<u>UNIT COST</u>	<u>TOTAL</u>
15.	New Paint Markings	---	LS	---	_____
16.	Site Utility Repair (Allowance)	---	LS	---	5,000.00
TOTAL:					\$ _____